

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-165-20196-00-00
Spot: SESENW Sec/Twnshp/Rge: 4-18S-18W
3000 feet from S Section Line, 3004 feet from E Section Line
Lease Name: ABELE Well #: 1
County: RUSH Total Vertical Depth: 3925 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 3550 | | |
| SURF | 8.625 | 511 | | WITH 310 SX CMT |
| PROD | 5.5 | 3918 | 0 | WITH 175 SX CMT |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/19/2012 9:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: OZZIE VANAUSDALE Company: GRESSEL OILFIELD SERVICE, LLC Phone: (316) 524-1225

Proposed Plugging Method: RUN TBG TO 3450'. PUMP 10 SX GEL & 50 SX CMT. PEFORATE 5 1/2" AT 1270' & 540'. RUN TBG TO 1300'. CIRCULATE CMT UP 5 1/2" & 8 5/8" X 5 1/2" ANNULUS.

Plugging Proposal Received By: STEVE DURRANT Witness Type: PARTIAL
Date/Time Plugging Completed: 01/20/2012 3:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

****WELL HAS CASING PARTED @ 3400' ACCORDING TO OPERATOR.**** RAN TBG TO 3470'. PUMPED 10 SX GEL & 50 SX CMT. PERFORATED 5 1/2" @ 1270' & 540'. RAN TBG TO 1302'. PUMPED 50 SX CMT. PULLED TBG TO 558' & PUMPED 200 SX CMT. HAD GOOD CIRCULATION TO START WITH UP STRINGS OF PIPE BUT LOST CIRCULATION. PULLED TBG OUT OF HOLE. SDON. 1/20/12: NO STATE WITNESS. TAGGED CMT INSIDE 5 1/2" @ 250' WITH TBG. CIRCULATED CMT TO SURFACE WITH 32 SX CMT. PULLED TBG & TOPPED OFF 5 1/2" WITH 3 SX CMT. PUMPED 150 SX CMT DOWN 8 5/8" X 5 1/2" ANNULUS. MAXIMUM PRESSURE 300 PSIG. INITIAL SHUT IN PRESSURE 250 PSIG.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|-------------|
| 3506 | 3510 | | KANSAS CITY |

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
FEB - 3 2012
KCC DODGE CITY

RECEIVED
FEB 13 2012

Form CP-27

KCC WICHITA