

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-081-20580-00-00  
Spot: NENESWSW Sec/Twnshp/Rge: 29-28S-32W  
1253 feet from S Section Line, 4024 feet from E Section Line  
Lease Name: MAXFIELD A Well #: 1  
County: HASKELL Total Vertical Depth: 5625 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4540		WITH 2 SX CMT
CIBP		5100		
CIBP		5260		
SURF	8.625	1793		WITH 850 SX CMT
PROD	5.5	5405	1835	WITH 175 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/26/2012 9:15 AM  
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC  
Proposal Rcvd. from: OZZY VANAUSDALE Company: GRESSEL OILFIELD SERVICES Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 4540' & 2 SX CMT. PLUG AT 1830' WITH 50 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: DANIEL BERNASCONI Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/26/2012 4:30 PM KCC Agent: DANIEL BERNASCONI

Actual Plugging Report:

1ST PLUG SET CIBP @ 4540' & 2 SX CMT. 2ND PLUG TIHWT TO 1844' & PUMPED 50 SX CMT. 3RD PLUG PTT 750'. PUMPED 50 SX CMT. NO RETURNS DECISION WAS MADE TO WASH-OUT 2ND PLUG. RAN TT 1100'. PUMPED 70 BBLS WATER TO FLUSH CASING. 4TH PLUG WAIT ON CMT 1.5 HOURS. TAG TOC @ 1827' WITH TBG. PUMP 75 SX CMT. 5TH PLUG PTT 773' & PUMP 50 SX CMT. 6TH PLUG PTT 42' & PUMP 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5278	5282		
5192	5210		
4596	4604		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED PREMIUM COMMON CEMENT BY COPELAND.

Plugged through: TBG

District: 01

RECEIVED  
FEB - 8 2012  
KCC DODGE CITY

Signed Daniel Bernasconi  
(TECHNICIAN)

RECEIVED  
FEB 13 2012  
KCC WICHITA Form CP-2/3

2/20/12