

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-02702-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 14-13S-17W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: KUHN B Well #: 2  
County: ELLIS Total Vertical Depth: 3493 feet

Operator License No.: 9067  
Op Name: DAMAR RESOURCES, INC.  
Address: 234 W 11TH STE A PO BOX 70  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| SURF   | 8.625 | 141        |             |          |
| PROD   | 5.5   | 3484       |             |          |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/08/2012 1:30 PM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: AVEN WEAVERLING Company: DAMAR RESOURCES INC. Phone: (785) 623-3221

Proposed Plugging Method: Emergency Plug with rig over hole.  
Ordered 200 sxs 60/40 poz mix 4% gel.  
8.625 - 141'; 5.5-3484'  
CIB @ 3150'  
Sqzd @ 628 w 150 sxs 10-7-2008; Sqzd @ 2224 W 250sxs 2-7-2012.  
Monroe packer @ 1180'  
DV tool @ 1170' never opened can't get packer above DV tool.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/08/2012 1:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perfs:

Perforators perfed @ 1150  
Express Well Service RIH with tubing to 1180' Swift rigged to tubing & mixed & pumped 135 sxs cement to circulate cement to surface.  
Operator lost 1180' of tubing in hole. Swift rigged to 5.5" CSG with a swedge & pumped 40 sxs with with 300 # PSI pressure fell to 0 #.  
Dug out 8.625 & found CSG to be full of cement.  
Topped off 5.5" CSG with 25 sxs. Well went on small vacuum.  
02-10-2012 topped off 5.5" CSG with 2 yards ready mix. Hole was standing full.

Remarks: SWIFT SERVICES TICKET 21401

Plugged through: TBG

District: 04

Signed \_\_\_\_\_

RECEIVED

(TECHNICIAN)

CM

FEB 13 2012

FEB 14 2012

KCC WICHITA

Form CP-2/3

2/20/12