

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-20173-00-00  
Spot: SENWNWSW Sec/Twnshp/Rge: 28-15S-35W  
2130 feet from S Section Line, 510 feet from W Section Line  
Lease Name: DIRKS C Well #: 1  
County: LOGAN Total Vertical Depth: 4495 feet

Operator License No.: 34513  
Op Name: BRITE LIQUIDS, LLC  
Address: 44915 CO RD T PO BOX 96  
CHEYENNE WELLS, CO 80810

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	856		500sx
PROD	5.5	4491		250sx

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/19/2012 10:00 AM  
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.  
Proposal Revd. from: PAUL DWYER Company: BRITE LIQUIDS, LLC Phone: (719) 342-0791

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement. 19 sx gel. 650# hulls. Plug through tubing.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/19/2012 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

DV tool @1500' w/400sx. Casing holes @3250'.  
Perforated casing @2495'.  
Ran tubing to 4400', pumped 1900# gel followed w/60sx cmt w/200# hulls.  
Pulled tubing to 3220', pumped 50 sx cmt w/150# hulls.  
Pulled tubing to 2480', pumped 40 sx cmt w/100# hulls.  
Pulled tubing to 1340', pumped 155 sx cmt w/200# hulls. Cement to surface.  
POOH. Connected to 5 1/2" casing and pumped 75sx cmt. Casing full.  
Connected to 8 5/8 surface casing. Pumped 5sx cmt. Casing head ruptured.

Remarks: CONSOLIDATED CEMENTING TICKET #33818

Plugged through: TBG

District: 04

Signed

*Darrel Dipman*

(TECHNICIAN)

CM

FEB 06 2012

RECEIVED

FEB 14 2012

KCC WICHITA

Form CP-2/3

✓ 2/20/12