

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40309-00-00
Spot: SWSW Sec/Twnshp/Rge: 17-23S-4E
1109 feet from S Section Line, 636 feet from W Section Line
Lease Name: LATHROP Well #: 3-6
County: BUTLER Total Vertical Depth: 2412 feet

Operator License No.: 5375
Op Name: HILLENBURG OIL CO., A GENERAL PA
Address: 11600 S LYNN LN RD
BROKEN ARROW, OK 74011

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.625	2185		
COND	8.25	1920		
PROD	5.5	235		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/23/2011 8:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: ANDY HILLENBURG Company: _____ Phone: (918) 455-4444

Proposed Plugging Method: RUN TUBING TO AT LEAST 2380 AND SET A 50 SX PLUG. PULL TUBING, WAIT AN HOUR, AND TAG TOP OF CEMENT. PERFORATE CASING AT 250' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/27/2011 1:00 PM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

Perfs:

RAN TUBING DOWN TO 2390' PUMPED 50 SX AND WAITED TO TAG UNTIL 12/27. TAGGED CEMENT WITH WIRELINE AT 2280'. PERFORATED WITH 4 SHOTS AT 250'. TIED ONTO CASING AND CIRCULATED WATER TO NEAR SURFACE (FLUID COULD BE SEEN APPROX. 15' DOWN IN THE CELLAR). PUMPED 475 SX AND STILL HAD NO RETURN TO SURFACE. RAN 1" DOWN BACK SIDE WHILE WASHING DOWN TO ROUGHLY 95' THEN LOST CIRCULATION. TIED BACK ONTO CASING AND PUMPED AND ADDITIONAL 225 SX AND CIRCULATED TO SURFACE. CONSOLIDATED TICKET #(BOTTOM): 31705. CONSOLIDATED TICKET #(TOP): 34139

Remarks: OLD CABLE TOOL HOLE WITH 17" HOLE. 3 OF 3 WELLS PLUGGED ON THE LATHROP.

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED

Form CP-2/3

FEB 17 2012

2/20/12

KCC WICHITA