

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-015-40311-00-00
Spot: NENESW Sec/Twnshp/Rge: 17-23S-4E
2449 feet from S Section Line, 2122 feet from W Section Line
Lease Name: LATHROP Well #: 27
County: BUTLER Total Vertical Depth: 2321 feet

Operator License No.: 5375
Op Name: HILLENBURG OIL CO., A GENERAL PA
Address: 11600 S LYNN LN RD
BROKEN ARROW, OK 74011

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	50		500 SX
PROD 7		2317		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/22/2011 10:00 AM
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC
Proposal Rcvd. from: ANDY HILLENBURG Company: _____ Phone: (918) 455-4444

Proposed Plugging Method: SET BOTTOM PLUG AT TD AND FILL TO 2265'. PULL UP TO 250' AND PUMP CEMENT TO SURFACE. CASING IS CEMENTED IN HOLE TOP TO BOTTOM WITH 500 SX.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/22/2011 10:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

Perfs:

RAN 2" TUBING TO 2315 AND PUMPED 75 SX OF 60 X 40 4% W/CALCIUM. WAITED 1 HOUR FOR CEMENT TO SET UP. RAN IN WITH WIRE LINE AND TAGGED CEMENT @ 2076. PULLED TUBING TO 510' AND PUMPED 140 SX OF CEMENT TO SURFACE AND TOPPED OFF. (TUBING WAS MEANT TO BE PULLED TO 270' BUT A MISCOUNT OF THE TUBING RESULTED IN A LARGER THAN EXPECTED TOP PLUG). CONSOLIDATED TICKET #31704.

Remarks: 1 OF 3 WELLS TO BE PLUGGED ON THE LATHROP LEASE

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED
FEB 17 2012
KCC WICHITA
Form CP-2/3
2/20/12

JK