

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-015-40310-00-00  
Spot: NWESW Sec/Twnshp/Rge: 17-23S-4E  
2290 feet from S Section Line, 1649 feet from W Section Line  
Lease Name: LATHROP S. LATHROP Well #: 20  
County: BUTLER Total Vertical Depth: 2413 feet

Operator License No.: 5375  
Op Name: HILLENBURG OIL CO., A GENERAL PA  
Address: 11600 S LYNN LN RD  
BROKEN ARROW, OK 74011

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10.75	800		100 SX
PROD	6.625	2411		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/23/2011 8:00 AM  
Plug Co. License No.: 6819 Plug Co. Name: SCOTT'S WELL SERVICE INC  
Proposal Rcvd. from: ANDY HILLENBURG Company: \_\_\_\_\_ Phone: (918) 455-4444

Proposed Plugging Method: RUN TUBING DOWN TO TOP OF KANSAS CITY @ 1950' AND SET A 50 SX PLUG. PERFORATE CASING AT 250' AND CIRCULATE CEMENT TO SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 12/23/2011 8:00 AM KCC Agent: PATRICK SHIELDS

Actual Plugging Report:

TUBING WAS RAN TO 1860' AND STACKED OUT. TIED ON SWIVEL AND WASHED OUT DOWN TO 1950' THEN PUMPED 75 SX OF 60 X 40 4% GEL 4% CALCIUM. WAITED ONE HOUR AND TAGGED PLUG AT 1710'. PERFORATED WITH 4 CHARGES AT 251'. TIED ON TO CASING AND CIRCULATE 175 SX TO SURFACE. APPEARED TO BE A CELLAR THAT WAS ALSO FILLED UP WITH CEMENT, EXPLAINS THE HIGH VOLUME NEEDED TO CIRCULATE TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2054	2057	TBG	
2044	2050	TBG	

Remarks: WELL HAD A PACKER CEMENT AND IN THE HOLE AND THE PBTD OF 2290' WAS NOT ON THE CP 1.

Plugged through: TBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

RECEIVED  
Form CP-2/3  
FEB 17 2012  
KCC WICHITA  
2/20/12