

1
100049

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,144-0000

NW SE NW, SEC. 18, T 17 S, R 28 **WAX**

3630 feet from ~~NW~~S section line
3630 feet from ~~NW~~E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Fuller Well # 1

Operator: Chief Drilling Co., Inc.

County Lane 148.79

Name & Address 905 Century Plaza

Well Total Depth 4578 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 347 ✓

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 18 Month: March Year: 19 85

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-262-3791

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2156' with 50 sx cement

2nd plug at 1376' with 50 sx cement

3rd plug at 750' with 40 sx cement

4th plug at 400' with 40 sx cement

5th & 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Blyse Wiley (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None _____ X--

Operations Completed: Hour: 4:30 am Day: 18 Month: March Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 2156' with 50 sx cement, 2nd plug at 1376' with 50 sx cement, 3rd plug at 750' with 40 sx cement, 4th plug at 400' with 40 sx cement, 5th 6th plug solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 7th plug to circulate rat hole with 15 sx cement, 8th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAR 25 1985
3-25-85
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
I will (not) observe this plugging.

DATE 3-28-85

Signed Blyse Wiley (TECHNICIAN)

INV NO. 7424