

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-21003-00-01
Spot: W2NESW Sec/Twnshp/Rge: 8-11S-18W
1980 feet from S Section Line, 1650 feet from W Section Line
Lease Name: CAVE Well #: 7
County: ELLIS Total Vertical Depth: 3564 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	212		185 SX
PROD	5.5	3618		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2012 2:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (316) 262-3596

Proposed Plugging Method: Ordered 625sx 60/40 pozmix 4% gel cement, 650# hulls

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/14/2012 6:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Perfs:

Tried to washdown well with pump and power swivel. Couldn't get past 1632'. Tubing stuck.
Pumped 265 sx cmt w/300# hulls.
Perforators shot off tubing @1306'. Pumped 200sx cmt w/200# hulls.
Pulled to 700'. Perfed casing @732'. POOH. Perfed @200'
02/14/2012 3:30 pm Witnessed by Pat Staab.
Tagged cmt @ 1088'. Plugged tubing. POOH. Ran tubing to 960' and circulated w/102 sx cmt w/150# hulls.
POOH. Topped off casing w/20sx cmt. Pumped 35sx cmt down backside. 100 psi MAX. Blew hole in head.

Remarks: QUALITY WELL SERVICE

Plugged through: TBG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

RECEIVED
FEB 28 2012
KCC WICHITA

FEB 16 2012

Form CP-2/3

✓ 3/07/12