

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-059-23174-00-01  
Spot: NWSENEW Sec/Twnshp/Rge: 33-15S-20E  
4483 feet from S Section Line, 3209 feet from E Section Line  
Lease Name: PAULINE SCOTT Well #: 10  
County: FRANKLIN Total Vertical Depth: 800 feet

Operator License No.: 5150  
Op Name: COLT ENERGY INC  
Address: PO BOX 388  
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	40		15 sx
PROD	2.5	800		65 SX

Well Type: EOR UIC Docket No: E24111.45 Date/Time to Plug: 02/02/2012 12:00 AM  
Plug Co. License No.: 5491 Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP  
Proposal Rcvd. from: COLT ENERGY, INC. Company: Phone: (620) 365-3111

Proposed Plugging Method: RIIH W/1" TBG TO BTM OF PROD CSG. PMP CMT TO SURFACE. POOH 1"TBG, TOP OFF WELL W/CMT AND PRESSURE SQUEEZE. RETURN AT A LATER DATE, DIG DOWN, CUT OFF CSG BELOW "PLOW" DEPTH

Plugging Proposal Received By: LEVI SHORT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 02/02/2012 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 1-INCH TO 800 FEET IN 2-1/2 INCH AND FILL TO SURFACE WITH CEMENT.  
PULL OUT 1-INCH, TOP OFF, THEN SQUEEZE. USE TOTAL OF 34 SACKS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
728	734		squirrel

RECEIVED

FEB 17 2012 LS


KCC Chanute Dist. #3

Remarks: FAILED MIT.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)

- cc to UIC 3/06/12

RECEIVED

Form CP-2/3

MAR 05 2012

3/07/12

KCC WICHITA