

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-191-21499-00-01 7
Spot: E2NWNENW Sec/Twnshp/Rge: 3-33S-2E
330 feet from N Section Line, 1850 feet from W Section Line
Lease Name: RUSH Well #: 1
County: SUMNER Total Vertical Depth: 3248 feet

Operator License No.: 5010
Op Name: KNIGHTON OIL COMPANY, INC.
Address: 1700 N WATERFRONT PKY BLDG 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	201		250 SX
T1	2.375	3219		
PROD	4.5	3248		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/22/2012 8:00 AM
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC
Proposal Rcvd. from: JOE BARNETT Company: GRESSELL OILFIELD SERVICE, LL Phone: (785) 623-4081

Proposed Plugging Method: CIBP 3130 & 2 SKS CMT. PERF 300' & CIRC CMT.

Plugging Proposal Received By: STEVE VANGIESON WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/11/2012 2:15 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

A CIBP WAS SET AT 3130' & CAPPED WITH 2 SKS CMT. NO RECOVERY. PERFD CASING AT 300', RAN TUBING TO 311' & CIRCD CEMENT INSIDE AND OUTSIDE OF 4 1/2 CASING.

Perfs:

Top	Bot	Thru	Comments
3183	3218	CSG	BARTLESVILLES S

RECEIVED
MAR 06 2012
KCC WICHITA

Remarks: COPELAND CMT. 135 SX CMT. TICKET #37858

Plugged through: TBG

District: 02

Signed _____

(TECHNICIAN)

✓ 2/07/12

✓ HX