

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-20024-00-00  
Spot: NESWSENW Sec/Twnshp/Rge: 3-21S-9W  
3165 feet from S Section Line, 3310 feet from E Section Line  
Lease Name: MOSHER Well #: 1  
County: RICE Total Vertical Depth: 2966 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S MAIN ST  
STAFFORD, KS 67578

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	207		200 SX
PROD	4.5	2960	2000	100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/22/2012 2:15 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKES TESTING & SALVAGE, INC. Phone: (620) 562-0895

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/22/2012 3:30 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, PULL TUBING AND RODS OUT. SAND TO 2890' AND CAP WITH 4 SX'S CEMENT. CUT CASING OFF AT 2000' AND PULL TO 1150' AND PUMP 35 SX'S, PULL CASING TO 750' AND PUMP 35 SX'S, PULL CASING TO 270' AND CIRCUALTE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
2960	2966	CSG	

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-39004. T.A. NEVER FILED BY RAMA.

Plugged through: CSG

RECEIVED

MAR 06 2012

KCC WICHITA

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

✓ 3/07/12

✓ 2K