

**Kansas Corporation Commission**  
**District Plugging Report**

API Well Number: 15-103-20,791 · 00 · 00  
 Spot: SESWSE Sec 2 Twp 10 S Rng 22  E /  W  
331 Feet from  N /  S Line of Section  
1708 Feet from  E /  W Line of Section  
 GPS: Lat: 39.202250 Long: 94.924860 Date: 10/5/07  
 Lease Name: DENNIS RYAN Well #: RYN 01  
 County: Leavenworth Total Vertical Depth: 1155 feet

Operator License No: <u>101</u>	String	Size	Depth	Pulled	Comments
Op Name: <u>STATE OF KANSAS</u>	<u>COND - Conductor Pipe</u>	<u>8.000</u>	<u>20</u>	<u>0</u>	<u>EST.</u>
Address 1: <u>130 S. MARKET</u>	<u>PROD - Casing</u>	<u>4.500</u>	<u>1,155</u>	<u>0</u>	
Address 2: _____	_____	_____	_____	_____	_____
City: <u>WICHITA</u>	_____	_____	_____	_____	_____
State: <u>KS</u> Zip Code: <u>67202</u> - _____	_____	_____	_____	_____	_____

Well Type: GAS - Natural Gas - Production UIC Docket No.: \_\_\_\_\_ Date/Time to Plug: 5/3/11 / 11:00 am  
 Plug Co License No.: 3097 Plug Co. Name: K-W OIL WELL SERVICES, INC.  
 Proposal Revd from: JIM KEPLEY Company Name: SAME Phone: (620) 431-2285

PUMP PORTLAND CEMENT FROM TDTO SURFACE.

KANSAS CORPORATION COMMISSION  
**MAY 20 2011**  
**RECEIVED**

Proposed  
Plugging  
Report:

Plugging Proposal Received By: FRANK GUILFOYLE Witness Type: COMP - Complete 100%  
 Date/Time Plugging Completed: 5/3/11 / 12:30 pm KCC Agent: FRANK GUILFOYLE

Actual Plugging Report:	Perfs:	Top	Bottom	Thru
CLEAR AROUND WELL. RUN 1" TO 900 FT INSIDE 4.5". RUN 1" OUTSIDE 4.5" TO 17 FT. PUMP PORTLAND CEMENT OUTSIDE TO SURFACE. PUMP CEMENT TO SURFACE INSIDE 4.5". PULL 1" AND TOP OFF WELL. PUMP TOTAL OF 106 SACKS OF PORTLAND CEMENT. DIG DOWN AND CUT OFF WELL. EMPTY AND BACKFILL PIT. LEVEL OUT AREA. WELL PLUGGED.	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____
	_____	_____	_____	_____

Remarks: CONTROL NUMBER 20110071-001. CONTRACT NUMBER 11781 REG. SEC.

Plugged Thru: TBG - Tubing Plugged Due to Compliance Issue:  Yes  No

District: 03  
 \_\_\_\_\_  
 (Technician)  
 Form: District Plugging Report - \_\_\_\_\_