

1041314

STATE CORPORATION COMMISSION

9-11

API NUMBER 15-007-20,679.00.00
100' E C NE NE SEC. 32, T 31 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 560 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME SIMPSON WELL # 1

TECHNICIAN'S PLUGGING REPORT COUNTY BARBER 139.27

OPERATOR LICENSE # 5393 WELL TOTAL DEPTH 4285 FEET

OPERATOR: A.L. ABERCROMBIE INC PRODUCTION CSG: SIZE 4 1/2 " FEET 4283

NAME AND RT 1 BOX 56 SURFACE CASING: SIZE 8 5/8" FEET 467'

ADDRESS GREAT BEND, KS 67530

ABANDONED OIL WELL GAS WELL X INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524

COMPANY TO PLUG AT: HOUR: 10:30 AM DAY: 11 MONTH: 09 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM BILL SOWELS

(COMPANY NAME) MIKE'S TESTING & SALVAGE, INC (PHONE) 316-938-2943

WERE: PERFS AT 4200-34 (PROD. PK @4190') PERFS 3920-24

1ST PLUG SAND BACK TO 3820' & PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER

2ND PLUG RUN 2 3/8" TUBING INTO 625'. CIRCULATE 4 1/2" CASING FROM 625' TO SURFACE WITH 45 SX

CEMENT. 3RD PLUG PULL TUBING OUT. PUMP DOWN 4 1/2"/8 5/8" ANNULAS WITH 5 SX CEMENT. PRESSURE

TO 600#.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 11:30 AM DAY: 11 MONTH: 09 YEAR: 1998

ACTUAL PLUGGING REPORT

1ST PLUG SANDED BACK TO 3820' & PUT 4 SX CEMENT ON TOP OF SAND BRIDGE THRU BAILER.

2ND PLUG RAN 2 3/8" TUBING INTO 625'. CIRCULATED 4 1/2" CASING FROM 625' TO SURFACE WITH 45 SX

CEMENT. 3RD PLUG PULLED TUBING OUT. PUMPED DOWN 4 1/2"/8 5/8" ANNULAS WITH 5 SX CEMENT.

PRESSURED TO 600#.

REMARKS: 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.

CEMENT IN BULL PLUG IN BRADEN LEAD ON 4 1/2"/8 5/8" ANNULAS. APPARENTLY MORE CMT RAN ON TOP STAGE & CEMENT CIRCULATED THEN FELL BACK.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE SEP 23 1998

SIGNED Stephen J. Pfeifer (TECHNICIAN) FORM CP-2/3

INV. NO. 51352

RECEIVED KANSAS CORP COM SEP 22 A 1 40