

1041395

STATE CORPORATION COMMISSION

API NUMBER 15-007-20,679 - 00-01  
100'E C NE NE SEC. 32, T 31 S, R 12 W

CONSERVATION DIVISION - PLUGGING SECTION 4620 FEET FROM NORTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 560 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME SIMPSON "OWWO" WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY BARBER 139.23

OPERATOR LICENSE # 31881

WELL TOTAL DEPTH 4284 FEET

OPERATOR: MCGINNESS OIL CO.

PRODUCTION CSG: SIZE 4 1/2" @ 4284' WITH SX

NAME AND ADDRESS 150 N MAIN #1026 WICHITA, KS 67202

SURFACE CASING: SIZE 8 5/8" @ 467' WITH SX

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A X

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR CLARKE CORPORATION LICENSE NUMBER 5105

ADDRESS PO BOX 187, MEDICINE LODGE, KS 67104

COMPANY TO PLUG AT: HOUR: 2:00 PM DAY: 24 MONTH: 05 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM ALAN VRATIL

(COMPANY NAME) CLARKE CORPORATION (PHONE) 316-886-5665

WERE: PERFS AT 2600-2603 & 2616-2622 CIBP @ 2660'. DV TOOL @ 2835 W/150 SX CEMENT.

SPOT PLUG THROUGH 2 3/8" TUBING INSIDE 4 1/2" CASING WITH 25 SX OF COMMON CEMENT WITH 3% CC AT

2558'. FILLED 4 1/2" CASING FROM 630' TO SURFACE THROUGH 2 3/8" TUBING USED 43 SX OF 60/40

POZMIX 6% GEL. 8 5/8"/4 1/2" ANNULUS IS CEMENTED BACK TO SURFACE. TOPPED OUT ANNULUS WITH 5 SX

CEMENT WHEN WELL WAS PLUGGED IN 1998. PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 4:00 PM DAY: 24 MONTH: 05 YEAR: 2000

ACTUAL PLUGGING REPORT

SPOT PLUG THROUGH 2 3/8" TUBING INSIDE 4 1/2" CASING WITH 25 SX OF COMMON CEMENT WITH 3% CC AT

2558'. FILLED 4 1/2" CASING FROM 630' TO SURFACE THROUGH 2 3/8" TUBING USED 43 SX OF 60/40

POZMIX 6% GEL. 8 5/8"/4 1/2" ANNULUS IS CEMENTED BACK TO SURFACE. TOPPED OUT ANNULUS WITH 5 SX

OF CEMENT WHEN WELL WAS PLUGGED IN 1998.

RECEIVED STATE CORPORATION

JUN 6 2000

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. NO CASING RECOVERED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED  
DATE 6/9/00  
INV. NO. 61850

SIGNED [Signature] for SPA  
(TECHNICIAN) FORM CP-2/3

(R)