

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

00-02 KCC
API Well Number: 15-015-22297-00-01
Spot: NENESW Sec/Twnshp/Rge: 29-25S-5E
2256 feet from S Section Line, 3019 feet from E Section Line
Lease Name: FINNEY I Well #: 76
County: BUTLER Total Vertical Depth: 2570 feet

Operator License No.: 5030
Op Name: VESS OIL CORPORATION
Address: 1700 WATERFRONT PKWY BLDG 500
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		920		
CIBP	4.5	1735		
SURF	8.625	259		175 SX
T1	2.375	709		
PROD	4.5	2569		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2012 8:00 AM
Plug Co. License No.: 32991 Plug Co. Name: SIMMONS WELL SERVICE, INC.
Proposal Rcvd. from: CASEY COATS Company: VESS OIL CORPORATION Phone: (316) 655-1997

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: NONE
Date/Time Plugging Completed: 02/02/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG, TAGGED PLUG @ 1735', WTBG @ 1730', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 75 SXS CLASS A COMMON 3% GEL, 2% CC AND DISPLACED IN CASING. POOH W/TBG. TAGGED CEMENT PLUG @ 1259'. RIH W/TBG @ 310', CONSOLIDATED WELL SERVICES ESTABLISHED CIRCULATION, MIXED & PUMPED 40 SXS CLASS A COMMON TO SURFACE. POOH W/TBG. TOPPED WELL BACK TO SURFACE W/10 SXS. CEMENT CIRCULATED. PLUG DOWN 5:00 P.M. 2-2-2012. CONSOLIDATED OILWELL SERVICES TICKET #36051.

Perfs:

Top	Bot	Thru	Comments
2478	2494	CSG	
1734	1734	CSG	
684	694	CSG	

Remarks: COMPLIANCE / DENIED TA/ ADMIRE PERFS 684'-694' SQUEEZED BACK.

Plugged through: TBG

RECEIVED

MAR 12 2012

KCC WICHITA

District: 02

Signed

Duane Krueger
(TECHNICIAN)