

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-21558-00-00
Spot: SWSENWSE Sec/Twnshp/Rge: 14-28S-33W
1349 feet from S Section Line, 1833 feet from E Section Line
Lease Name: BARBEE GRANGER Well #: 1-14
County: HASKELL Total Vertical Depth: 5636 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4720		WITH 2 SX CMT
SURF	8.625	1876		WITH 610 SX CMT
PROD	4.5	5000	2011	WITH 175 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/21/2012 3:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4720' WITH 2 SX CMT. PLUG AT 1900' WITH 20 SX GEL & 50 SX CMT. PLUG AT 720' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 02/21/2012 6:00 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

SET CIBP @ 4720' WITH 2 SX CMT. 1ST PLUG AT 1914' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 726' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4825	4833		
4770	4776		

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC WELL CEMENTERS.

Plugged through: TBG

District: 01

Signed Eric MacLaren
(TECHNICIAN)

RECEIVED
MAR - 7 2012
KCC DODGE CITY

RECEIVED
MAR 12 2012
KCC WICHITA

Form CP-2/3

3/13/12

RAW