

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-053-20643-00-01
Spot: NWNENW Sec/Twnshp/Rge: 8-16S-10W
4958 feet from S Section Line, 3588 feet from E Section Line
Lease Name: WHITE Well #: 4 SWD
County: ELLSWORTH Total Vertical Depth: 3600 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: 3118 CUMMINGS RD PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	306		185 SX
T1	2.375	1385	1385	
PROD	4.5	3322		150 SX

Well Type: SWD UIC Docket No: D25743.0 Date/Time to Plug: 02/29/2012 9:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELL SERVICE, INC.
Proposal Rcvd. from: KEVIN WILES SR Company: AMERICAN WARRIOR, INC. Phone: (620) 272-4996

Proposed Plugging Method: CASING LEAK @ 1330', TOP OF FIBERGLASS TUBING FISH @ 1385'.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/29/2012 1:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU WITH EXPRESS WELL SERVICE, ATTEMPT TO PULL TUBING -- PULLED APART AT 1385'. ATTEMPT TO MILL TUBING FISH -- POSSIBLY GOT OUTSIDE OF CASING AT 1385'. EXPRESS WELL SERVICE RIGGED DOWN. ON 2-29-12, CHASE WELL SERVICE RIGGED UP, ATTEMPTED TO RUN IN TUBING -- COULD ONLY GET TO 1293'. PERFORATE AT 1075' AND 360'. PUMPED 35 SX'S COMMON CEMENT WITH 3% CC AT 1293' --PULLED TUBING UP 550' AND LET SET FOR 1 HR. RUN TUBING BACK DOWN AND TAGGED CEMENT AT 787'. PULL TUBING UP TO 360' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. PUMPED CEMENT DOWN BACKSIDE OF 4.5" -- PRESSURED UP TO 250#S. SHUT DOWN AND TOPPED OFF CASING AGAIN.

Perfs:

Top	Bot	Thru	Comments
3322	3600	OH	OH ABRUCKLE

Remarks: PLUGGED DUE TO FAILED MIT. PIONEER WIRELINE # 1-39079. ALLIED TICKET #42491.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

RECEIVED
MAR 12 2012
KCC WICHITA

cc to MC 3/12/12

Form CP-2/3

3/13/12

1/2