

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-071-20020-00-01  
Spot: SE Sec/Twnshp/Rge: 13-19S-41W  
1326 feet from S Section Line, 1365 feet from E Section Line  
Lease Name: CAMPBELL OWWO Well #: 1  
County: GREELEY Total Vertical Depth: 2950 feet

Operator License No.: 4894  
Op Name: HORSESHOE OPERATING, INC.  
Address: 110 W LOUISIANA STE 200  
MIDLAND, TX 79701

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2825		WITH 2 SX CMT
SURF	10.75	357		WITH 300 SX CMT
PROD	4.5	2962	0	WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/23/2012 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: LARRY Company: HORSESHOE OPERATING Phone: (432) 683-1448

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KAREN J. RITTER Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/23/2012 3:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2825' WITH 2 SX CMT. PERFORATE AT 1450'. SET CMT RETAINER AT 1400'. STING INTO RETAINER WITH 2 3/8" TBG. INJECTION RATE 2 BPM @ 1100 PSI. PUMP 100 SX CMT VIA TBG THROUGH RETAINER (80 SX OUT PERFS). NO BLOW OR CIRCULATION UP ANNULUS. STING OUT OF RETAINER & SPOT 20 SX CMT ON TOP OF RETAINER. PULL TBG TO 1000' & CIRCULATE CASING FULL OF CMT USING 80 SX CMT. TOOH W/TBG. TOP OFF 4 1/2" CASING WITH 45 SX CMT. STAYED FULL. PUMP 250 SX CMT DOWN 4 1/2" X 10 3/4" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2904	2910		
2875	2886		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA HIGH FL\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed

(TECHNICIAN)

RECEIVED  
MAR - 7 2012  
KCC DODGE CITY

RECEIVED  
MAR 12 2012

KCC WICHITA

Form CP-2/3

3/13/12