

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-10233-00-00  
Spot: SWSWNSW Sec/Twnshp/Rge: 18-27S-12W  
1589 feet from S Section Line, 3634 feet from E Section Line  
Lease Name: SICU Well #: 17  
County: PRATT Total Vertical Depth: 4334 feet

Operator License No.: 31739  
Op Name: IUKA-CARMI DEVELOPMENT LLC  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4130		
SURF	8.625	832		WITH 475 SX CMT
PROD	5.5	4334	0	WITH 200 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/01/2012 9:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: SET CIBP @ 4130' & PUT 2 SX CMT ON TOP OF CIBP. PERFORATE 5 1/2" CASING @ 860'. CIRCULATE 5 1/2" X 8 5/8" ANNULUS & FILL 5 1/2" CASING WITH CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 03/05/2012 11:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4130' & PUT 2 SX CMT ON TOP OF CIBP THRU DUMP BAILER. PERFORATE 5 1/2" CASING AT 860'. ATTEMPT TO PUMP DOWN 5 1/2" CASING WITH WATER TO ESTABLISH CIRCULATION UP 5 1/2" X 8 5/8" ANNULUS. PRESSURED UP TO 1000#. ESTABLISHED RATE OF 1.5 BPM @ 850#. ANY INCREASE IN RATE PRESSURE WOULD CLIMB. DID NOT ESTABLISH CIRCULATION. RAN BOND LOG & FOUND NO CMT ON BACKSIDE OF 5 1/2" CASING. DID FIND WHAT APPEARED TO BE A BRIDGE ON BACKSIDE OF CASING AT 750'. REPERFORATE 5 1/2" CASING @ 862'. 3/2/12: SET CMT RETAINER @ 822'. RUN TBG IN & STING INTO CMT. RETAINER. CMT THROUGH RETAINER WITH 50 SX CMT. RATE @ 1.5 BPM @ 750#. MAXIMUM PRESSURE 800#. PRESSURE BROKE BACK TO 600#. PULLED OUT OF CMT RETAINER & PUT 3 SX CMT ON TOP OF RETAINER. LAY DOWN TBG. 3/5/12: RUN BOND LOG. SET DOWN @ 486'. FOUND NO CMT BEHIND 5 1/2" CASING. PERFORATE W/4 SHOTS PER FOOT @ 470' TO 471'. PUMPED DOWN 5 1/2" CASING WITH 125 SX CMT CIRCULATING 5 1/2" X 8 5/8" ANNULUS & FILLING 5 1/2" CASING WITH CMT.

Perfs:

Top	Bot	Thru	Comments
4290	4298		
4215	4240		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA 10 YR RULE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Stephen J. Sparta  
(TECHNICIAN)

3/13/12

RECEIVED

MAR - 7 2012

KCC DODGE CITY

RECEIVED

MAR 12 2012

KCC WICHITA

Form CP-2/3