

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21701-01-01
Spot: W2NWNE Sec/Twnshp/Rge: 28-32S-34W
775 feet from N Section Line, 2483 feet from E Section Line
Lease Name: HITCH S Well #: 2
County: SEWARD Total Vertical Depth: 6640 feet

Operator License No.: 5447
Op Name: OXY USA INC.
Address: 5 E GREENWAY PLZ PO BOX 27570
HOUSTON, TX 77227

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5900		WITH 2 SX CMT
CIBP		6190		WITH 2 SX CMT
SURF	8.625	1731		WITH 455 SX CMT
DVT		3022		
L1	6.5	6238		
PROD	5.5	6639	0	WITH 740 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/28/2012 10:00 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP @ 5900' WITH 2 SX CMT. PLUG AT 3050' WITH 20 SX GEL & 20 SX CMT. PLUG AT 1760' WITH 30 SX CMT. PLUG AT 580' WITH 30 SX CMT. PLUG AT 40' TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/28/2012 2:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PER 5 1/2" STRETCH, TOC @ APPROXIMATELY 300'. SET CIBP@ 5900' WITH 2 SX CMT. 1ST PLUG RIH W/TBG TO 3050' & CIRCULATED HOLE WITH MUD. PUMPED 30 SX CMT AT 3050'. 2ND PLUG AT 1760' WITH 30 SX CMT. 3RD PLUG AT 580' WITH 30 SX CMT. 4TH PLUG AT 90' WITH 10 SX CMT. BACKSIDE WAS FULL OF MUD, UNABLE TO GET WITH 1" PIPE.

Perfs:

Top	Bot	Thru	Comments
6238	6640		OPEN HOLE
6194	6196		CHESTER
6114	6146		CHESTER
6011	6018		WINDOW IN 5-1/2

RECEIVED
MAR 12 2012
KCC WICHITA

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

District: 01

RECEIVED
MAR - 7 2012
KCC DODGE CITY

Signed

Jack MacLaskey
(TECHNICIAN)

3/13/12
BWT