

Operator Name: Raymond Oil Company, Inc. Lease Name: Brack Well #: 1
 Sec. 21 Twp. 20 S. R. 35 East West County: Wichita

INSTRUCTIONS: Show important tops and base of formations penetrated. Detail all cores. Report all final copies of drill stems tests giving interval tested, time tool open and closed, flowing and shut-in pressures, whether shut-in pressure reached static level, hydrostatic pressures, bottom hole temperature, fluid recovery, and flow rates if gas to surface test, along with final chart(s). Attach extra sheet if more space is needed. Attach copy of all Electric Wireline Logs surveyed. Attach final geological well site report.

Drill Stem Tests Taken <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Attach Additional Sheets)</i> Samples Sent to Geological Survey <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Cores Taken <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No Electric Log Run <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No <i>(Submit Copy)</i> List All E. Logs Run: IND Log N-D Log Micro Log Sonic Log	<input checked="" type="checkbox"/> Log Formation (Top), Depth and Datum <input type="checkbox"/> Sample <table style="width:100%; border-collapse: collapse;"> <tr> <td style="width:60%;">Name</td> <td style="width:20%;">Top</td> <td style="width:20%;">Datum</td> </tr> <tr> <td>B/Anh</td> <td>2304</td> <td>+873</td> </tr> <tr> <td>Heeb</td> <td>3976</td> <td>-799</td> </tr> <tr> <td>B/KC</td> <td>4484</td> <td>-1307</td> </tr> <tr> <td>Atoka</td> <td>4786</td> <td>-1609</td> </tr> <tr> <td>Miss</td> <td>4968</td> <td>-1791</td> </tr> </table>	Name	Top	Datum	B/Anh	2304	+873	Heeb	3976	-799	B/KC	4484	-1307	Atoka	4786	-1609	Miss	4968	-1791
Name	Top	Datum																	
B/Anh	2304	+873																	
Heeb	3976	-799																	
B/KC	4484	-1307																	
Atoka	4786	-1609																	
Miss	4968	-1791																	

CONFIDENTIAL

FEB 09 2010

KCC

CASING RECORD <input checked="" type="checkbox"/> New <input type="checkbox"/> Used							
Report all strings set-conductor, surface, intermediate, production, etc.							
Purpose of String	Size Hole Drilled	Size Casing Set (in O.D.)	Weight Lbs. / Ft.	Setting Depth	Type of Cement	# Sacks Used	Type and Percent Additives
Surface	12 1/4"	8 5/8"	24#	249	common	260	3% cc, 2% gel
Production	7 7/8"	5 1/2"	14#	5093	60/40 pozmix	230	7% salt
2nd Stage				2114	Lite	450	

ADDITIONAL CEMENTING / SQUEEZE RECORD				
Purpose:	Depth Top Bottom	Type of Cement	#Sacks Used	Type and Percent Additives
<input type="checkbox"/> Perforate				
<input type="checkbox"/> Protect Casing				
<input type="checkbox"/> Plug Back TD				
<input type="checkbox"/> Plug Off Zone				

Shots Per Foot	PERFORATION RECORD - Bridge Plugs Set/Type		Acid, Fracture, Shot, Cement Squeeze Record	
	Specify Footage of Each Interval Perforated		(Amount and Kind of Material Used)	
4	4854-60	Atoka SD	AC, 500 gal 15%	4854-60
4	4650-55	Myric Sta	AC, 500 gal 15%	4650-55
4	4534-42	Marm B	AC, 500 gal 15%	4534-42
-	4820	Bridge Plug		

TUBING RECORD: Size: 2" Set At: 4811 Packer At: _____ Liner Run: Yes No

Date of First, Resumed Production, SWD or Enhr. _____ Producing Method: Flowing Pumping Gas Lift Other (Explain) _____

Estimated Production Per 24 Hours	Oil Bbls. <u>140</u>	Gas Mcf _____	Water Bbls. <u>40-50</u>	Gas-Oil Ratio _____	Gravity _____
-----------------------------------	----------------------	---------------	--------------------------	---------------------	---------------

DISPOSITION OF GAS: <input type="checkbox"/> Vented <input type="checkbox"/> Sold <input type="checkbox"/> Used on Lease <i>(If vented, Submit ACO-18.)</i>	METHOD OF COMPLETION: <input type="checkbox"/> Open Hole <input checked="" type="checkbox"/> Perf. <input type="checkbox"/> Dually Comp. <input type="checkbox"/> Commingled <input type="checkbox"/> Other (Specify) _____	PRODUCTION INTERVAL: <u>Marm B, Myric Sta</u>
---	---	--

ALLIED CEMENTING CO., LLC. 044326

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT:

Dick (L) K

DATE <i>10/18/09</i>	SEC.	TWP. <i>20</i>	RANGE <i>35</i>	CALLED OUT	ON LOCATION <i>11:00pm</i>	JOB START <i>2:30 AM</i>	JOB FINISH <i>3:00 AM</i>
LEASE <i>Brack</i>	WELL # <i>1</i>	LOCATION <i>Scott City 870 Scott Finney CL</i>			COUNTY <i>Scott</i>	STATE <i>Ks</i>	
OLD OR NEW <input checked="" type="radio"/> (Circle one)			<i>16W 3N 1/2 W Sinto</i>			Wichita	

CONTRACTOR *Tomcat Drilling #3*

TYPE OF JOB *5 in Face*

HOLE SIZE *12 1/2* T.D. *255*

CASING SIZE *8 7/8* DEPTH *252*

TUBING SIZE DEPTH

DRILL PIPE DEPTH

TOOL DEPTH

PRES. MAX MINIMUM

MEAS. LINE SHOE JOINT

CEMENT LEFT IN CSG. *15'*

PERFS.

DISPLACEMENT *15.028*

OWNER *Same*

CEMENT AMOUNT ORDERED *170 SKs Com 390 CC*

2 00 gel

COMMON	<i>170 SK</i>	@	<i>15.45</i>	<i>2626.50</i>
POZMIX		@		
GEL	<i>3.9 SK</i>	@	<i>20.00</i>	<i>62.40</i>
CHLORIDE	<i>0.4 SK</i>	@	<i>82.00</i>	<i>349.20</i>
ASC		@		

EQUIPMENT

PUMP TRUCK CEMENTER *Alan*

422 HELPER *Wayne*

BULK TRUCK # *377* DRIVER *Labene*

BULK TRUCK # DRIVER

RECEIVED

FEB 10 2010

KCC WICHITA

HANDLING	<i>179 SK</i>	@	<i>2.40</i>	<i>429.60</i>
MILEAGE	<i>104 SK/mile</i>			<i>1432.00</i>
CONFIDENTIAL				TOTAL <i>4899.20</i>

REMARKS:

Cement did NOT circulate

FEB 09 2010
KCC SERVICE

*Max 170 SKs cement did NOT circulate
Had circulation i.e. while mixing or
Displacing Plug*

*I thank you
Alan, Wayne, Labene*

DEPTH OF JOB	<i>255</i>
PUMP TRUCK CHARGE	<i>101.80</i>
EXTRA FOOTAGE	@
MILEAGE	<i>80</i> @ <i>7.00</i> <i>560.00</i>
MANIFOLD	@

CHARGE TO: *Raymond Oil*

STREET _____

CITY _____ STATE _____ ZIP _____

TOTAL *1578.00*

To Allied Cementing Co., LLC.
You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PLUG & FLOAT EQUIPMENT

<i>8 5/8 wooden Plug</i>	@	<i>68.00</i>
	@	
	@	
	@	
	@	
TOTAL <i>68.00</i>		

PRINTED NAME _____

SIGNATURE *Dick (L) K*

SALES TAX (If Any) _____

TOTAL CHARGES _____

DISCOUNT _____ IF PAID IN 30 DAYS

