

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-207-27870-00-00

Spot: SWSWSENW

Sec/Twnshp/Rge: 19-26S-17E

2475 feet from N Section Line,

3795 feet from E Section Line

Lease Name: DWIGHT JACKSON

Well #: 4

County: WOODSON

Total Vertical Depth: 1075 feet

Operator License No.: 34243

Op Name: KING, CHARLES DBA CK OIL

Address: 409 E. WILSON

YATES CENTER, KS 66783

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
<u>SURF</u>	<u>7</u>	<u>20</u>		

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/30/2012 12:00 AM

Plug Co. License No.: 5491

Plug Co. Name: W & W PRODUCTION COMPANY, GENERAL PARTNERSHIP

Proposal Rcvd. from:

Company:

Phone:

Proposed
Plugging
Method:

Plugging Proposal Received By:

WitnessType: NONE

Date/Time Plugging Completed 01/30/2012 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down to TD. Mixed and pumped gel down the 1" pipe. Pumped cement through the 1" pipe at TD and placed a 75' plug. Pulled 1" pipe up to the Kansas City formation. Pumped cement through the 1" pipe and placed a 75' plug at the base of the Kansas City. Pulled up to 250'. Pumped and circulated cement through the 1" pipe from 250' to surface. Pulled the rest of the 1" pipe. Topped well off with cement. A total of 98 sacks of portland cement was reported used to plug this well.

RECEIVED

FEB 16 2012 RMD

KCC Chanute Dist. #3

RECEIVED

FEB 23 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

[Signature]
(TECHNICIAN)

✓ 2/28/12