

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15046-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 29-16S-11W
2310 feet from N Section Line, 330 feet from W Section Line
Lease Name: ESFELD Well #: 1
County: BARTON Total Vertical Depth: 3150 feet

Operator License No.: 32098
Op Name: CLASSIC WELL SERVICE, INC.
Address: BOX 539
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	504		75 SX
PROD	4.5	3295		75 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/07/2012 12:00 PM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: FRED L. BECK Company: CLASSIC WELL SERVICE, INC. Phone: (620) 587-3402

Proposed Plugging Method: Ordered 320 sx 60/40 pozmix 4% gel cement.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/08/2012 10:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 3000' and pumped 100sx cmt.
Pulled tubing to 1500' and pumped 60sx cmt.
Pulled tubing to 750' and pumped 120sx cmt. Ran out of cmt.
Shut down 2 hrs.
Pumped 120sx cmt. No circulation. Shut down for day.
2/8/2012 Ran in tubing and tagged cmt @450'. Pumped 50sx cmt. Circulated to surface. POOH

Remarks: COPELAND ACID AND CEMENT

Plugged through: TBG

RECEIVED
FEB 23 2012
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

FEB 10 2012

Form CP-2/3

✓ 2/28/12