

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-15047-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 29-16S-11W
1650 feet from N Section Line, 330 feet from W Section Line
Lease Name: ESFELD Well #: 3
County: BARTON Total Vertical Depth: 3308 feet

Operator License No.: 32098
Op Name: CLASSIC WELL SERVICE, INC.
Address: BOX 539
CLAFLIN, KS 67525

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
SURF	7	558		130 SX
PROD	4.5	3295		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/08/2012 3:00 PM
Plug Co. License No.: 32098 Plug Co. Name: CLASSIC WELL SERVICE, INC.
Proposal Rcvd. from: FRED L. BECK Company: CLASSIC WELL SERVICE, INC. Phone: (620) 587-3402

Proposed Plugging Method: Ordered 320sx 60/40 4% gel cement.
Junk in hole @2100'.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/09/2012 10:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfs:

Ran tubing to 2100' and pumped 60sx cmt.
Pulled tubing to 1200' and pumped 50sx cmt.
Pulled tubing to 450' and pumped 290sx cmt. Ran out of cmt.
Shut down for day.
2/9/2012 Tagged cmt w/tubing @480. Tied to tubing and pumped 50sx cmt. Circulated to surface. POOH.

Remarks: COPELAND ACID AND CEMENT

Plugged through: TBG

RECEIVED
FEB 23 2012
KCC WICHITA

District: 04

Signed Bruce Rodie
(TECHNICIAN)

cr

Form CP-2/3

FEB 10 2012

2/20/12