

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21198-00-00
Spot: SENE Sec/Twnshp/Rge: 2-33S-34W
3300 feet from S Section Line, 660 feet from E Section Line
Lease Name: BLACK Well #: C-2
County: SEWARD Total Vertical Depth: 6613 feet

Operator License No.: 4419
Op Name: BEAR PETROLEUM, LLC
Address: PO BOX 438
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		2950		WITH 5 SX CMT
CIBP		5661		
SURF	8.625	1661		WITH 775 SX CMT
PROD	5.5	5783	1710	WITH 205 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/02/2012 9:00 AM
Plug Co. License No.: 34367 Plug Co. Name: LONESTAR SERVICES LLC
Proposal Rcvd. from: DICK SCHREMMER Company: BEAR PETROLEUM Phone: (316) 524-1225

Proposed Plugging Method: SET CIBP @ 2950' WITH 5 SX CMT. SHOOT CASING & POH WITH CASING. RIH W/TBG TO 1690' & PUMP 20 SX MUD & 50 SX CMT. 40 SX CMT AT 600'. 20 SX CMT AT 40'.

Plugging Proposal Received By: RICHARD LACEY WitnessType: NONE
Date/Time Plugging Completed: 02/02/2012 5:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 2950' WITH 5 SX CMT. 1ST PLUG RIH W/TBG TO 1685' & PUMP 20 SX GEL, 50 SX CMT & 100# HULLS. 2ND PLUG AT 600' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5664	5666		
5632	5648		

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

Signed Richard M. Lacey
(TECHNICIAN)

RECEIVED
FEB 15 2012
KCC DODGE CITY

RECEIVED
FEB 23 2012
KCC WICHITA

Form CP-2/3
2/28/12
RAM