

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-19243-00-00
Spot: NESWSW Sec/Twnshp/Rge: 27-19S-9W
934 feet from S Section Line, 4373 feet from E Section Line
Lease Name: SLEDD I F C Well #: 2
County: RICE Total Vertical Depth: 3207 feet

Operator License No.: 32846
Op Name: PREMIER OIL & EXPLORATION INC
Address: 1100 AIRPORT RD
HUTCHINSON, KS 67501

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	10	207		
PROD	5.5	3173	1616	

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/20/2012 2:45 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE KELSO TEST Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL
Date/Time Plugging Completed: 02/20/2012 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:
MIRU CK BOTTOM. SAND PERFS AND OPEN HOLE TO 2890', AND CAP WITH 5 SX'S CEMENT. CUT CASING AT 1616' AND PULL TO 1125' AND PUMP 35 SX'S CEMENT. PULL CASING TO 750' AND PUMP 35 SX'S. PULL CASING TO 260' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3173	3207	OH	OPEN HOLE
2940	2946	CSG	CASING

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-35974. PLUGGED DUE TO DENIED TA - HFLDL.
Plugged through: CSG

District: 02 Signed Virgil Clothier
(TECHNICIAN)

RECEIVED
FEB 27 2012
KCC WICHITA
Form CP-2/3
3/01/12