

FIVE CUS

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-119-21063-00-00  
Spot: SENWSE Sec/Twnshp/Rge: 15-34S-30W  
1656 feet from S Section Line, 1671 feet from E Section Line  
Lease Name: CIMARRON Well #: 1-15  
County: MEADE Total Vertical Depth: 3502 feet

Operator License No.: 30337  
Op Name: SPECIAL ENERGY CORP.  
Address: PO BOX 369  
STILLWATER, OK 74076

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3165		WITH 2 SX CMT
SURF	8.625	704		WITH 100 SX CMT
COND	20	50		WITH 6 SX CMT
PROD	4.5	3501	2492	WITH 125 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/17/2012 9:00 AM  
Plug Co. License No.: 34271 Plug Co. Name: KIVETT PLUGGING & PIPE PULLING, INC.  
Proposal Rcvd. from: KENNETH KIVETT Company: KIVETT PLUGGING & PIPE PULLI Phone: (580) 363-3036

Proposed Plugging Method: SET CIBP @ 3165' WITH 2 SX CMT. PLUG AT 1700' WITH 50 SX CMT. PLUG AT 740' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/17/2012 2:00 PM KCC Agent: KENNY SULLIVAN

**Actual Plugging Report:**

CIBP @ 3165' WITH 2 SX CMT. 1ST PLUG AT 1716' WITH 50 SX CMT. TBG STUCK IN HOLE. SHOT TBG AT 803'. 2ND PLUG AT 743' WITH 50 SX CMT WITH VERY LITTLE RETURNS. TAGGED CMT AT 705'. RAN TBG IN HOLE & SPOTTED 25 SX CMT. 3RD PLUG AT 30' WITH 10 SX CMT. CMT CIRCULATED TO SURFACE.

**Perfs:**

Top	Bot	Thru	Comments
3215	3219		

Remarks: \*\*COMPLIANCE ISSUE: NOV TA LTR\*\* USED COMMON CEMENT BY ACIDIZING CEMENTING SERVICES.

Plugged through: TBG

District: 01

RECEIVED  
FEB 17 2012  
KCC DODGE CITY

Signed [Signature]  
(TECHNICIAN)

RECEIVED  
FEB 27 2012  
KCC WICHITA

Form CP-58