

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-19243-00-00  
Spot: NESWSW Sec/Twnshp/Rge: 27-19S-9W  
934 feet from S Section Line, 4373 feet from E Section Line  
Lease Name: SLEDD I F C Well #: 2  
County: RICE Total Vertical Depth: 3207 feet

Operator License No.: 32846  
Op Name: PREMIER OIL & EXPLORATION INC  
Address: 1100 AIRPORT RD  
HUTCHINSON, KS 67501

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| SURF   | 10   | 207        |             |          |
| PROD   | 5.5  | 3173       | 1616        |          |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/20/2012 2:45 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: JAMIE HARRIS Company: MIKE KELSO TEST Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: PATRICK SHIELDS Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/20/2012 5:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU CK BOTTOM. SAND PERFS AND OPEN HOLE TO 2890', AND CAP WITH 5 SX'S CEMENT. CUT CASING AT 1616' AND PULL TO 1125' AND PUMP 35 SX'S CEMENT. PULL CASING TO 750' AND PUMP 35 SX'S. PULL CASING TO 260' AND CIRCULATE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

| Top  | Bot  | Thru | Comments  |
|------|------|------|-----------|
| 3173 | 3207 | OH   | OPEN HOLE |
| 2940 | 2946 | CSG  | CASING    |

Remarks: 60-40 POZ, 4% GEL. COPELAND TICKET #C-35974. PLUGGED DUE TO DENIED TA - HFLDL.

Plugged through: CSG

District: 02

Signed

Virgil Clothier  
(TECHNICIAN)

RECEIVED

FEB 27 2012

Form CP-2/3

✓ 3/01/12

KCC WICHITA

JK