

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22356-00-00
Spot: NWSESENE Sec/Twnshp/Rge: 28-27S-12W
1982 feet from N Section Line, 358 feet from E Section Line
Lease Name: SABCO BERGNER Well #: 1-28
County: PRATT Total Vertical Depth: 4560 feet

Operator License No.: 34148
Op Name: SABCO OPERATING CO.
Address: 34 S. WYNDEN
HOUSTON, TX 77056

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|-----------------|
| CIBP | | 3700 | | WITH 2 SX CMT |
| CIBP | | 3842 | | |
| CIBP | | 3931 | | |
| CIBP | | 4006 | | |
| CIBP | | 4050 | | |
| SURF | 8.625 | 391 | | WITH 300 SX CMT |
| PROD | 5.5 | 4399 | 2590 | WITH 275 SX CMT |

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 02/16/2012 1:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2534

Proposed Plugging Method: FILL HOLE WITH MUD OR GELLED WATER THROUGH TBG. SPOT 50 SX CMT ON BOTTOM THROUGH TBG. SHOOT OFF 5 1/2" CASING & LAY DOWN. RUN TBG TO 900'. FILL HOLE WITH MUD OR GELLED WATER. 1ST PLUG AT 900' WITH 50 SX CMT. 2ND PLUG AT 420' WITH 60 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/17/2012 9:00 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 3700' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 910' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 40 SX CMT. CMT DID NOT CIRCULATE ON LAST PLUG. SDON. 2/17/12: TAG TOC @ 118'. TOP OUT 8 5/8" WITH 35 SX CMT.

Perfs:

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 4134 | 4170 | | |
| 4014 | 4018 | | |
| 3938 | 3944 | | |
| 3850 | 3855 | | |
| 3714 | 3722 | | |

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID & CEMENT.

Plugged through: CSG

District: 01

RECEIVED
FEB 23 2012
KCC DODGE CITY

Signed

Stephen J Pfeifer
(TECHNICIAN)

RECEIVED
FEB 27 2012
KCC WICHITA

3/01/12