

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20867-00-00
Spot: NWNESENE Sec/Twnshp/Rge: 27-22S-4E
3949 feet from S Section Line, 636 feet from E Section Line
Lease Name: JENSEN Well #: 8
County: MARION Total Vertical Depth: 2485 feet

Operator License No.: 5610
Op Name: BRUCE OIL COMPANY, L.L.C.
Address: 1704 LIMESTONE RD
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	167		125 SX
PROD	5.5	2482	1550	50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/10/2012 9:00 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: LONNY BRUCE Company: BRUCE OIL COMPANY Phone: _____

Proposed Plugging Method: DUMP SAND TO 50' ABOVE PERFORATIONS. CAP W/4SX CEMENT. RIP CASING AND PULL. BUILD BRIDGE @250' AND FILL WITH SLURRY MIX.

Plugging Proposal Received By: _____ WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 02/10/2012 11:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:

2/10/12 SUNFLOWER HAD LAID OUT WELL AND DROPPED SAND & TAGGED @ 2360' AND CAPPED W/5 SX. THEY RIPPED CASING @ 1550' AND LAID IT OUT THE PREVIOUS DAY. THEY BUILT A BRIDGE @ 275'. HILLSBORO REDEMIX OUT AND DUMPED 2+ YARDS OF SLURRY MIX TK #47438. 2/15/12 I CHECKED TOP PLUG FOUND IT DOWN ABOUT 21'. I CONTACTED LEVI KOEHN W/BRUCE OIL. THEY WILL TOP OF THE WELL WHEN THEY CUT OFF CASING.

Perfs:

Top	Bot	Thru	Comments
2447	2451	CSG	
2433	2434	CSG	

Remarks: DENIED TA DUE TO 10YEAR RULE. PBTD 2482'

Plugged through: CSG

District: 02

Signed _____

(TECHNICIAN)

RECEIVED

FEB 27 2012

Form CP-2/3

3/01/12

KCC WICHITA

JK