

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-30038-00-00
Spot: S2NESW Sec/Twnshp/Rge: 19-14S-13W
1650 feet from S Section Line, 3300 feet from E Section Line
Lease Name: EHRlich Well #: 16
County: RUSSELL Total Vertical Depth: 3195 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	754		420 SX
PROD	5.5	3184		260 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/23/2012 11:00 AM
Plug Co. License No.: 34318 Plug Co. Name: BEREXCO LLC
Proposal Rcvd. from: CURT GABEL Company: BEREXCO LLC Phone: (785) 623-0546

Proposed Plugging Method: Ordered 500sxs 60/40 poz 4% gel;500# hulls
CSG leaks 1250' & 1425'
Hole in CSG @ 20'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/23/2012 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech-perfed 2 shot holes @ 1250' & 745'
Berexco RIH with tubing to 3019. Quality rigged to tubing & pumped 100sxs with 300# hulls mixed in.
Pulled tubing to 2013' Quality rigged to tubing & mixed & pumped 230 sxs with 200 # hulls mixed in circulate cement up 5.5" CSG.
Pulled tubing rigged to 8.625" CSG with a swedge & pumped 35 sxs to circulate cement up 5.5" CSG, shut in valves & pressured CSG to 100# PSI SIP 100#.

Perfs:

Top	Bot	Thru	Comments
3006	3012		LKC
2991	2993		LKC
2984	2986		LKC
2953	2957		LKC
2941	2944		LKC
2930	2932		LKC
2918	2920		LKC
2808	2810		PLATTSMOUTH

Remarks: (31925) QUALITY WELL SERVICES TICKET # 5442

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

FEB 27 2012

Form CP-2/3

3/01/12

RECEIVED
FEB 28 2012
KCC WICHITA