

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-25658-00-00  
Spot: W2SESWSE Sec/Twnshp/Rge: 29-17S-13W  
330 feet from S Section Line, 1970 feet from E Section Line  
Lease Name: MARY ANNE Well #: 1-29  
County: BARTON Total Vertical Depth: 3450 feet

Operator License No.: 31725  
Op Name: SHELBY RESOURCES LLC  
Address: 445 UNION BOULEVARD SUITE 208  
LAKEWOOD, CO 80228

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	817		

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/27/2012 12:00 AM  
Plug Co. License No.: 5142 Plug Co. Name: STERLING DRILLING COMPANY  
Proposal Rcvd. from: LANNIE Company: STERLING DRILLING COMPANY Phone: \_\_\_\_\_

Proposed Plugging Method: Ordered 190 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS WitnessType: NONE  
Date/Time Plugging Completed: 02/27/2012 1:00 AM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3350 w/25 sx  
2nd plug @875 w/50 sx  
3rd plug @375 w/60 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx Mousehole 15 sx

Perfs:

Remarks: QUALITY OILWELL CEMENTING

Plugged through: DP

RECEIVED  
FEB 28 2012  
KCC WICHITA

District: 04

Signed Case Morris  
(TECHNICIAN)

FEB 27 2012

✓ 3/01/12