

TO:
STATE CORPORATION COMMISSIO
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 6720

API Well Number: 15-011-22065-00-00
Spot: SWNENWNE Sec/Twnshp/Rge: 9-24S-22E
4735 feet from S Section Line, 1870 feet from E Section Line
Lease Name: DANIELS-DAVIS-ZEEBECK Well #: 9-2
County: BOURBON Total Vertical Depth: 550 feet

Operator License No.: 30944
Op Name: THYER, JOE DBA D & T OIL COMPAN
Address: PO BOX 141
BLUE MOUND, KS 66010

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	20		5 sx
PROD	2.5	550		60 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 09/24/2011 12:00 AM
Plug Co. License No.: 31519 Plug Co. Name: JACKSON, LELAND DBA LONE JACK OIL CO.
Proposal Rcvd. from: JOE THYER Company: _____ Phone: (620) 363-1140

Proposed Plugging Method: Fill with cement from TD to surface.

Plugging Proposal Received By: _____ WitnessType: NONE
Date/Time Plugging Completed 09/24/2011 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Ran 1" pipe down the inside of the 2.5" casing to TD. Circulated cement through the 1" pipe inside the 2.5" casing from TD to surface. Pulled 1" pipe up to 200'. Circulated cement through the 1" pipe from 200' to surface. Pulled the rest of the 1" pipe out and topped well off with cement. A total of 20 sacks of portland cement was reported used to plug this well.

RECEIVED

FEB 24 2012

KCC Chanute Dist. #3

RMD

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

3/02/12

RECEIVED Form CP-2/3

FEB 29 2012

KCC WICHITA