

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-035-20742-00-00  
Spot: SENENE Sec/Twnshp/Rge: 24-32S-4E  
4555 feet from S Section Line, 401 feet from E Section Line  
Lease Name: MAGNUSSON Well #: 2  
County: COWLEY Total Vertical Depth: 2370 feet

Operator License No.: 33277  
Op Name: COOPER, ALBERT L. DBA COOPER SER  
Address: PO BOX 381  
WINFIELD, KS 67156

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	150		150 SXS
PROD	4.54	2365		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 12/28/2011 8:00 AM  
Plug Co. License No.: 33277 Plug Co. Name: COOPER, ALBERT L. DBA COOPER SERVICE CO.  
Proposal Rcvd. from: ALBERT L. COOPER Company: COOPER SERVICE Phone: (316) 204-0072

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK Witness Type: PARTIAL  
Date/Time Plugging Completed: 01/23/2012 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/WORKSTRING CIRCULATING VARIOUS BRIDGES & HOLE CLEAN @ 436'. LAYED DOWN WORK STRING. RIH ON WIRELINE W/IMPRESSION BLOCK, POOH W/WIRELINE IMPRESSION BLOCK DID NOT TELL ANYTHING. 12/30/11, RIH W/WORKSTRING & DRILL BIT DRILLED 20', @ 456'. DRILLING ON STEEL. POOH W/WORKSTRING. RIH W/FISH COULD NOT GET UNTO ANYTHING. RIH W/WORKSTRING & TAPORED COLLAR & SPEAR VARIOUS TIMES, POOH W/PACKER RUBBER, PVC PIPE, & POLY PIPE. RIH W/WORKINGSTRING & MILL, CIRCULATING METAL SCHAVINGS OUT OF WELL. 1/13/12, RIH ON WIRELINE SHOT SQUEEZE HOLES @ 390'-391'. 1-23-12, RIH W/TBG @ 390', MCPHERSON DRILLING MIXED & PUMPED 36 SXS CLASS A COMMON 390'-0'. CEMENT CIRCULATED. RIH W/1" ON BACKSIDE @ 35', MCPHERSON DRILLING PUMPED 2 SXS CLASS A COMMON TO SURFACE. TOPPED WELL OFF W/2 SXS. MCPHERSON DRILLING TICKET #21321. TOPPED WELL BACK TO SURFACE W/2 SXS CLASS A COMMON. P & A COMPLETE.

Perfs:

Top	Bot	Thru	Comments
2342	2342	CSG	

Remarks: COMPLIANCE / 10 YR TA RULE

Plugged through: TBG

District: 02

Signed

*Duane Krueger*

(TECHNICIAN)

3/01/12

RECEIVED  
Form CP-2/3  
FEB 29 2012

KCC WICHITA