

1 070279

JAN 0 6 1987

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Operator: Donald C. Slawson  
Name & Address: 200 Douglas Building  
Wichita, KS 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12:30 p.m. Day: 6 Month: 1 Year: 19 87

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-659-3165

were: 4 1/2" at 4649' PBD 4590' Perfs at 4332-37' Elevation 2786' KB

1st plug sand back to 4280' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:30 p.m. Day: 6 Month: 1 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4280' and dumped 4 sx cement, on top of sand through bailer,

2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls,

released 8 5/8" wiper plug and pumped 150 sx cement.

STATE CORPORATION COMMISSION

JAN 9 1987

CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Recovered 1400' of 4 1/2" casing. Used 60/40 Pozmix 6% gel by Allied.  
(if additional description is necessary, use BACK of this form.)

**INVOLCED**  
observe this plugging.

DATE 1-20-87

Signed Dan Goodson  
(TECHNICIAN)

INV. NO. 15946