

To: 1 031264 3-15
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

APL NUMBER 15- 101-20,369-0000
SW SE NE, SEC. 6, T 17 S, R 28 W/X
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30083
Operator: G.A.B.S. Oil Company
Name: G.A.B.S. Oil Company
Address 321 E. Magnolia
Ness City, KS 67560

Lease Name James "B" Well # 1
County Lane
Well Total Depth 4575 148.68 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Plains License Number 4072
Address P.O. Box 346, Ness City, KS 67560-0346

Company to plug at: Hour: 11 a.m. Day: 15 Month: 3 Year: 19 94

Plugging proposal received from Clint Base
(company name) Plains (phone) 913-798-3995

were: 4 1/2" at 4572' w/150 sx cement, Perfs at 4328-31'
1st plug spot plug at top of perfs,
2nd plug perforate casing at 1300' and pump casing volume plus 80 sx cement,
3rd plug pump 170 sx cement down backside.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2:45 p.m. Day: 15 Month: 3 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug ran tubing to 2200', bridged, could not circulate down,
pulled up to 1900', spotted 25 sx cement,
2nd plug perforated at 1350' and squeezed with 150 sx cement. Shut in 100 psi.
3rd plug squeezed backside with 200 sx cement. Maximum pressure 200 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

DATE 3-22-94
INV. NO. 40135
3-15

Signed Steve Durrant
(TECHNICIAN) Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION

MAR 18 1994