

To: 1 070371
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-17-87
API NUMBER 15-101-21,384-0000

TECHNICIAN'S PLUGGING REPORT

SE NW NW, SEC. 6, T 17 S, R 28 W/E
4290 feet from S section line
4290 feet from E section line

Operator License # 4661

Lease Name Terwilliger Well # 1-6

Operator: Galloway Petroleum Exploration, Inc. County Lane
Name & Address 360 Broadway Plaza Bldg.
Wichita, KS 67202

County Lane 151.13
Well Total Depth 4650 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 363

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Galloway Drilling Company, Inc. License Number 5783

Address 340 Broadway Plaza, 105 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 4 a.m. Day: 17 Month: 7 Year: 19 87

Plugging proposal received from Carl McGuire

(company name) Galloway Drilling Company Inc. (phone) 316-263-1793

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2783'
Anhydrite 2185-2215'

1st plug at 2215' with 50 sx cement, 2nd plug at 1600' with 90 sx cement,

3rd plug at 390' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:15 a.m. Day: 17 Month: 7 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2215' with 50 sx cement,

2nd plug at 1600' with 90 sx cement,

3rd plug at 390' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
JUL 21 1987
7-21-87
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
(did not observe this plugging.)

Signed Dan Goodrow
(TECHNICIAN)

DATE 7-22-87

INV. NO. 17590

7-17