

12-1-87

To: 1 070479
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-21,441-0000
C SW NW, SEC. 7, T 17 S, R 28 W/E
3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4661 Lease Name James Well # 1-7
Operator: Galloway Petroleum Exploration, Inc. County Lane 149.50
Name & Address 360 Broadway Plaza Bldg. Well Total Depth 4600 feet
Wichita, KS 67202 Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 345

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Galloway Drilling Company, Inc. License Number 5783

Address 340 Broadway Plaza, 105 South Broadway, Wichita, KS 67202

Company to plug at: Hour: 11:30 a.m. Day: 1 Month: 12 Year: 19 87

Plugging proposal received from Carl McGuire

(company name) Galloway Drilling Company, Inc. (phone) 316-263-1793

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2772'
Anhydrite 2175-2205'

1st plug at 2200' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,
3rd plug at 375' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 1:30 p.m. Day: 1 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,
2nd plug at 1350' with 80 sx cement,
3rd plug at 375' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
12-7-87
DEC 7 1987

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.) CONSERVATION DIVISION
Wichita, Kansas

Observe this plugging.

INVOICED
DATE 12-8-87 Signed Dan Galloway
(TECHNICIAN)

INV. NO. 19200 12-1