

5-15

1 070810

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,766-0000

NW NW SE, SEC. 7, T 17 S, R 28 W/E

2310 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Terwilliger B Well #1

Operator: Chief Drilling Company, Inc.
Name & Address 224 East Douglas, #530
Wichita, KS 67202

County Lane 149.79

Well Total Depth 4609 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 290

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Company License Number 5883

Address 224 East Douglas, #530, Wichita, KS 67202

Company to plug at: Hour: 10:30 a.m. Day: 15 Month: 5 Year: 19 90

Plugging proposal received from Gary Lindenmuth

(company name) Warrior Drilling Company (phone) 316-262-3791

were: 4 1/2" at 4603' Perfs at 4209-4549'

1st plug pump 2 sx hulls and fill to surface with light cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Handwritten notes:
KCC
90
5-22-90
S-70-101

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 15 Month: 5 Year: 1990

ACTUAL PLUGGING REPORT 1st plug pumped 400 lbs. hulls and 200 sx cement down 4 1/2", went on vacuum.

2nd plug pumped 250 lbs. hulls down backside with 70 sx cement. Maximum pressure 1000 psi and shut in 1500 psi.

3rd plug pumped 350 lbs. hulls and 100 sx cement down 4 1/2". Maximum pressure 1000 psi and shut in 1000 psi.

Remarks: Used 65/35 Pozmix 8% gel by Allied. No casing recovery. 4 1/2" was set w/ 750 SX
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-30-90

Signed Dan Goodson
(TECHNICIAN)

INV. NO. 28285