

1 090553

6-8

API NUMBER 15- 101-20,802 -0000

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE NE SW, SEC. 7, T 17 S, R 28 W/EX

2310 feet from S section line

2970 feet from E section line

Lease Name James A Well # 1

County Lane

Well Total Depth 4587 149.08 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Allied Cementing License Number

Address

Company to plug at: Hour: 11:30 a.m. Day: 8 Month: 6 Year: 1995

Plugging proposal received from Mike

(company name) Chief Drilling, Inc. (phone) 316-262-3791

were: 4 1/2" at 4581' w/200 sx cement, PBTD 4270', Perfs at 4531-39, 4505-07, 4487-89;  
4471-72, 4226-31'

1st plug sand back to 4180' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 50 sx cement at 2180', 3rd plug pump 80 sx cement at 1350',

4th plug pump 40 sx cement at 650', 5th plug pump 40 sx cement at 310', 6th plug pump 10

sx cement at 40'. Plugging Proposal Received by Richard Lacey

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1 p.m. Day: 8 Month: 6 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 2300' and dumped 5 sx cement on top of sand

through bailer,

2nd plug perforated casing at 1350' and pumped 225 sx cement down casing. Maximum pressure

500 psi and shut in 200 psi.

3rd plug hooked onto backside and pumped 150 sx cement. Maximum pressure 500 psi and shut

in 150 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED

Signed [Signature] (TECHNICIAN)

DATE 6-14-95

INV. NO. 42964