

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,873-0000

SE SW NE, Sec. 7, T 17 S, R 28 W/E

330 feet from N/S section line

990 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Terwilliger Well # C-1

Operator: Chief Drilling Co., Inc.
Name & 905 Century Plaza
Address Wichita, KS 67202

County Lane

Well Total Depth 4595 feet 149.33

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 343

316-262-3791 called 3-20-84

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Co. #2 License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: 10:00 pm Day: 27 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Marion Burris

(company name) Warrior (phone) 316-653-7716

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 2100' with 50 sx cement

2nd plug at 1260' with 50 sx cement

3rd plug at 390' with 50 sx cement

solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement.

7th plug to circulate mousehole with 10 Signed Paul A. Luthi

sx cement. (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 12:01 am Day: 28 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2100' with 50 sx cement, 2nd plug at 1260' with

50 sx cement, 3rd plug at 390' with 50 sx cement, 4th & 5th plugs solid bridge -

hulls, plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate

rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel, 3% cc. by Allied Cementing

RECEIVED
STATE CORPORATION COMMISSION
2-2-84
FEB 02 1984
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated
and that I (~~did~~ / did not) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

INVOICED

DATE 2-6-84

INV. NO. 00666

1-28