

To: 1 052047

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, KS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422

Operator: Abercrombie Drilling, Inc.

Name & Address 150 N. Main, Ste. 801

Wichita, KS 67202

API NUMBER 13- 101-21,721-0000

E/2 NE NE, SEC. 7, T 17 S, R 28 W/E

5-31

660 feet from NSK section line

330 feet from E section line

Lease Name Terwilliger Well # 1

County Lane 150.15

Well Total Depth 4620 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 355

Abandoned Oil Well Gas Well Input Well SHD Well D&A X

Other well as hereinafter indicated

Abercrombie RTD, Inc.

Plugging Contractor License Number 30684

Address 150 N. Main, Ste. 801, Wichita, KS 67202

Company to plug at: Hour: 11 a.m. Day: 31 Month: 5 Year: 19 96

Plugging proposal received from Tony Martin

(company name) Abercrombie RTD, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2215-2285

1st plug at 2200' with 50 sx cement, 2nd plug at 1400' with 80 sx cement,

3rd plug at 700' with 40 sx cement, 4th plug at 380' with 50 sx cement,

5th plug at 40-0' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 2 p.m. Day: 31 Month: 5 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,

2nd plug at 1400' with 80 sx cement, 3rd plug at 700' with 40 sx cement,

4th plug at 380' with 50 sx cement, RECEIVED

KANSAS CORPORATION COMMISSION

5th plug at 40-0' with 10 sx cement, JUN 11 1996

6th plug to circulate rathole with 15 sx cement, 6-11-96

7th plug to circulate mousehole with 10 sx cement. CONSERVATION DIVISION

WICHITA KS

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED  
(Exxx did not) observe this plugging.

Signed Richard W. Lacey  
(TECHNICIAN)

DATE JUN 19 1996

45811

5-31