

1 070390

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,388-0000

NW NE SE , SEC. 8 , T 17 S, R 28 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Operator: Mull Drilling Company, Inc.

Name & Address P.O. Box 2758

Wichita, KS 67201

2310 feet from S section line

990 feet from E section line

Lease Name Terwilliger Well # 1

County Lane 149.21

Well Total Depth 4591 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 324

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:30 p.m. Day: 17 Month: 8 Year: 19 87

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4585' Perfs at 4182-4290'

1st plug sand back to 4440' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 100 lbs. hulls, 60 sx ATL cement down 8 5/8",

3rd plug pump 300 lbs. hulls and 190 sx ATL cement down 5 1/2".

Plugging Proposal Received by Paul Luthi & Dan Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 3 p.m. Day: 17 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4130' and dumped 5 sx cement on top of sand through bailer, 5 1/2" pipe shot at 1400',

2nd plug pumped 100 lbs. hulls and 60 sx ATL cement down 8 5/8", Maximum pressure 500 psi

3rd plug cement pumped through shot hole at 1400', and shut in 200 psi.

4th plug pumped 300 lbs. hulls and 190 sx ATL cement down 5 1/2", Maximum pressure 1000 psi and shut in 200 psi.

Remarks: Used ATL cement by Allied. No recovery.  
(if additional description is necessary, use BACK of this form.)

INVOICED (copy to observe this plugging.)

DATE 8-21-87

INV. NO. 17905

Signed Dan Goodrow  
(TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION

8-19-87  
AUG 19 1987