

1 050885

MAR 1 0 1987

API NUMBER 15- 101-21,368-~~0000~~

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SW SW, SEC. 8, T 17 S, R 28 W/E

330 feet from S section line

4950 feet from E section line

Lease Name Terwilliger Well # 1

County Lane Lane 150.31

Well Total Depth 4625' feet

Conductor Pipe: Size 8 feet 215

Surface Casing: Size 8 5/8 feet 215

TECHNICIAN'S PLUGGING REPORT

Operator License # 4629

Operator: Brito Oil Company, Inc.

Name & Address 200 East First, Suite 413

Wichita, KS 67202

Wichita, KS 67202

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Lobo Drilling Company License Number 5864

Address Box 877, Great Bend, KS 67530

Company to plug at: Hour: 4 p.m. Day: 10 Month: 3 Year: 19 87

Plugging proposal received from Ervin Neighbors

(company name) Lobo Drilling Company (phone) 316-792-7476

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2780'  
Anhydrite 2169-98'

1st plug at 2200' with 50 sx cement, 2nd plug at 1350' with 80 sx cement,

3rd plug at 250' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 7 p.m. Day: 10 Month: 3 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 2200' with 50 sx cement,

2nd plug at 1350' with 80 sx cement,

3rd plug at 250' with 50 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(if additional description is necessary, use BACK of this form)

observe this plugging.

DATE 3-20-87

INV. NO. 16345

Signed Richard W. Lacey  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
3-18-87  
MAR 18 1987  
CONSERVATION DIVISION  
Wichita, Kansas