

To: 1 070392
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,430 - 0000
SW SE NE, SEC. 8, T 17 S, R 28 W/E^{XX}
2970 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5144
Operator: Mull Drilling Company, Inc.
Name & Address P.O. Box 2758
Wichita, KS 67201

Lease Name Terwilliger Well # 2
County Lane 149.34
Well Total Depth 4595 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well Gas Well Input Well SWD Well D&A
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 4 p.m. Day: 17 Month: 8 Year: 19 87

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 4 1/2" at 4595' Perfs at 4146-4542'

1st plug sand back to 4100' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 150 sx econolite down 4 1/2",
3rd plug pump 100 sx econolite down 8 5/8".

Plugging Proposal Received by Paul Luthi & Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 5 p.m. Day: 17 Month: 8 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug sanded back to 4090' and dumped 4 sx cement on top of
sand through bailer, 4 1/2" pipe shot at 1400',
2nd plug pump 20 sx ATL followed by 130 sx ATL with 400 lbs. hulls mixed in first half
down 4 1/2", Maximum pressure 1000 psi and shut in 500 psi,
3rd plug pumped 100 sx ATL down 8 5/8", Maximum pressure 250 psi and shut in 50 psi.

RECEIVED
STATE CORPORATION COMMISSION
AUG 19 1987
8-19-87

Remarks: Used ATL by Allied. No recovery.
(If additional description is necessary, use BACK of this form.)

INVOICED
Date 8-21-87 observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE 8-21-87
INV. NO. 17904