

1030186

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,967-~~0000~~

NW NW SW, SEC. 8, T 17 S, R 28 W

2310 feet from ~~W/S~~ section line

330 feet from ~~W/S~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5144

Lease Name Terwilliger Well # 3

Operator: Mull Drilling Company

County Lane

Name & Address P. O. Box 2758

Well Total Depth 4650 151.13 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Company License Number 6033

Address 617 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 5:30 pm Day: 11 Month: May Year: 19 84

Plugging proposal received from Marvin Jullian

(company name) Murfin (phone) 316-267-3241

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2280' with 50 sx cement 2nd plug at 1280' with 50 sx cement

3rd plug at 720' with 50 sx cement 4th plug at 300' with 50 sx cement
solid bridge

5th plug hulls - plug at 40' -- cement to surface with 10 sx cement

7th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Shumant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 11:30 pm Day: 11 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement, 2nd plug at 1280' with 50

sx cement, 3rd plug at 720' with 50 sx cement, 4th plug at 300' with 50 sx cement, 5th

& 6th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement.

7th plug to circulate rat hole with 10 sx cement.

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton.

If additional description is necessary, use BACK of this form

(I did not) observe this plugging.

RECEIVED STATE CORPORATION COMMISSION MAY 25 1984 CONSERVATION DIVISION Wichita, Kansas

INVOICED

DATE 5-29-84

INV. NO. 1684

5-11

Signed Steve Shumant (TECHNICIAN)