

1 050456

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 101-20,279-0000

NW NE NW, SEC. 12, T 17 S, R 28 (W)E

4950 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5393

Lease Name Schneider Well # 1

Operator: A. L. Abercrombie, Inc.

County Lane 151.13

Name & Address 801 Union Center

Well Total Depth 4650 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 325

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 9:00 am Day: 19 Month: February Year: 1985

Plugging proposal received from Ron Hoover

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4354' PBD 4319', Perfs at 4268-74'

1st plug sand back to 4210' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls, and 125 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 am Day: 19 Month: February Year: 1985

ACTUAL PLUGGING REPORT 1st plug sanded back to 4210' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 15 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED STATE CORPORATION COMMISSION 2-25-85 FEB 25 1985

Maximum pressure 400 psi and shut in 200 psi

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Sun.

(If additional description is necessary, use BACK of this form.)

INVOICED

(did observe this plugging.)

DATE 2-27-85

Signed Richard W. Lacey (TECHNICIAN)

INV. NO. 71618

2-19