

1 060199

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-101-20,934-0000

SE NE SW, SEC. 16, T 17 S, R 28 W

1660 feet from N/S section line

2340 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Towns 'F' Well # 1

Operator: Donald C. Slawson

County Lane

Name & Address 200 Douglas Building

Well Total Depth 4630 150.48 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 469

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address 200 Douglas Building, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 10 Month: March Year: 19 84

Plugging proposal received from Ron Rouse

(company name) Slawson (phone) 316-263-3201

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 2120' with 50 sx cement

2nd plug at 1360' with 50 sx cement

3rd plug at 520' with 50 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement, 7th plug to circulate mousehole with 10 sx cement
Plugging Proposal Received by Paul A. Lulke (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:00 pm Day: 10 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 2120' with 50 sx cement, 2nd plug at 1360' with

50 sx cement, 3rd plug at 520' with 50 sx cement, 4th & 5th plugs - solid bridge- hulls -

plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rathole with

15 sx cement, 7th plug to circulate mousehole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Halliburton

(if additional description is necessary, use BACK of this form.)

(do not) observe this plugging.

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1984
3-19-84
CONSERVATION DIVISION
WICHITA, Kansas

Signed Paul A. Lulke (TECHNICIAN)

INVOICED

DATE 3-22-84

INV. NO. 0890
3-10