

TO:  
STATE CORPORATION COMMISSIO  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 6720

API Well Number: 15-207-19867-00-00  
Spot: SWSWNWSE Sec/Twnshp/Rge: 24-23S-16E  
1499 feet from S Section Line, 2445 feet from E Section Line  
Lease Name: REMLINGER/GLEUE Well #: 4  
County: WOODSON Total Vertical Depth: 990 feet

Operator License No.: 34047  
Op Name: RON-BOB OIL LLC  
Address: PO BOX 41  
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	6.5	20		20 SX
PROD	2.375	965		20 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/18/2011 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: ROBERT CHRISTENSON Company: \_\_\_\_\_ Phone: (620) 365-0919

Proposed Plugging Method: RUN 1" INTO 2" TO BOTTOM AND RUN 1" BEHIND 2" TO BOTTOM, THEN CEMENT FROM BOTTOM TO SURFACE.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed 10/19/2011 8:00 AM KCC Agent: RYAN DULING

**Actual Plugging Report:**

Ran 1" pipe down the inside of the 2 3/8" casing to TD. Ran 1" pipe down the backside of the 2 3/8" casing inside the 6.5" casing to 700'. Pumped and circulated cement through the 1" pipe inside the 2 3/8" casing from TD to surface. Pulled 1" pipe inside the 2 3/8" casing to 500'. Pumped cement through the 1" pipe on the backside of the 2 3/8" casing inside the 6.5" casing from 700' to surface. Pulled 1" pipe on the backside to 250'. Pumped cement through the 1" pipe inside the 2 7/8" casing from 500' to surface. Pulled the 1" pipe inside the 2 7/8" casing to 250'. Pumped cement through the 1" pipe outside the 2 7/8" casing inside the 6.5" casing from 250' to surface. Pulled the rest of the 1" pipe from the backside. Pumped cement through the 1" pipe inside the 2 7/8" casing from 250' to surface. Pulled the rest of the 1" pipe out of the 2 7/8" casing. Topped well off with cement. A total of 108 sacks of portland cement was reported used to plug this well.

Perfs:

RECEIVED

FEB 23 2012

RECEIVED

FEB 16 2012 RMD

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

KCC WICHITA

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

Form CP-2/3

✓ 2/28/12